

Name of Work : Aluminium sheet works in Hospital kitchen of VPSV Ayurveda college, Kottakkal.
TENDER SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
1	280.00 kg	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	kg					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
2	50.00 m ²	Providing at all heights, levels and locations Aluminium profile industrial troughed sheet of Alloy 31500/31000/40800, conforming to IS 1254, IS 737, IS 2676. The sheet shall be fixed using self drilling/self tapping SS screws of size 5.5x65 mm with EPDM seal complete upto required pitch in horizontal, vertical or curved surfaces i/c cutting to size and shape where required as per specifications, detail drawings and direction of Engineer-in-Charge. The rate shall be inclusive of all screws, seal, ridge, labour, scaffolding, machinery for fixing and approved sealent where required etc. but excluding the cost of purlins, rafters and trusses. 0.40 mm thick, the profile detail width 1044/920 mm, cover width 1000/875 mm.	m ²					
3	19.00 m	Supplying and fixing best quality PVC square type gutter 200 mm or nearest size with necessary all fittings	m					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
4	2.00 Nos	Supplying and fixing best quality PVC End drop including cost and conveyance of materials and labour charge etc.	E					
5	2.00 Nos	Supplying and fixing best quality PVC Middle drop including cost and conveyance of materials and labour charge etc.	E					
6	24.00 Nos	Supplying and fixing MS pathy clamp.	E					
7	11.00 m ²	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work .	m ²					
						TOTAL		

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5	6	7		
		<p>Note: 1.In case any obvious mistake the schedule of the item which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during period of contract .</p>						

CONTRACTOR

CHIEF EXECUTIVE OFFICER