

Name of Work :Providing Parking facilities to PG blocks Agada tandra and Dravya Guna in VPSV Ayurveda college, Kottakkal
TENDER SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
1	370.00m ²	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	m ²					
2	40.00m ³	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	m ³					
3	1.00m ³	Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc	m ³					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5	6	7		
4	2.00m ³	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	m ³					
5	385.00 m ²	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	m ²					
					TOTAL			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

