

Name of Work :Temporary Shed (Phase 3)
TENDER SCHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	0.807 cum	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	cum			
2	11.200 sqm	5.9.3 Centering and shuttering including strutting, etc. and removal of form for:Suspended floors, roofs, landings, balconies and access platform	sqm			
3	64.000 kilogram	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	kg			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
4	50.000 sqm	13.1.2 12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand).	sqm			
5	0.800 cum	5.1.3 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum			
					GRAND TOTAL	

CONTRACTOR

CHIEF EXECUTIVE OFFICER

