

**Name of Work :RENOVATION TO GREEN HOUSE SHED IN HERBAL GARDEN IN VPSV
AYURVEDA COLLEGE KOTTAKKAL
TENDER SHEDULE**

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure Rs.	In words	Rs.
1	2	3	4	5	6	7
1	0.162m ²	2.1.1 Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed:All Kinds of soil	sqm			
2	0.64 cum	50.6.7.1 Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc.	cum			
3	70 sqm	13.1.1 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	sqm			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
4	50.08 kg	50.10.2 Steel work for purlin/single section with G I pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	kg			
5	65 sqm	13.99.1 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work	sqm			
6	40 sqm	5.21 Extra for providing and fixing expanded metal mesh of size 20x60 mm and strands 3.25 mm wide 1.6 mm thick weighing 3.64 kg per sqm for encasing or rolled steel sections in beams, columns and grillages excluding cost of hangers.	sqm			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
7	40.506 sqm	12.47.1 Providing & fixing UV stabilised fibre glass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8 mm dia G.I plain/ bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovings incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified. 2 mm thick corrugate 2.5" or 4.2" or 6") or step-down (2' or 3" or 6") as specified.	sqm			
					GRAND TOTAL	
		Note: 1 .In case any obvious mistake the schedule of the item which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during period of contract .				

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7

CONTRACTOR

CHIEF EXECUTIVE OFFICER