

Name of Work : Prevention of water leakage on General female ward and top of deluxe payward room no 301 in hospital building
TENDER SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount	
				In figure	In words	Rs.	
				Rs.		Rs.	
1	2	3	4	5	6	7	
1	215 sqm	22.6 Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying : a) after surface preparation, first layer of slurry of cement @ 0.488 kg/ sqm mixed with water proofing cement compound @ 0.253 kg/ sqm. laying second layer of fibre glass cloth when the first layer is still green. Overlaps of joints of fibre cloth should not be less than 10 cm. c) third layer of 1.5 mm thickness consisting of slurry of cement @ 1.289 kg/ sqm mixed with water proofing cement compound @ 0.670 kg/sqm and coarse sand @ 1.289 kg/sqm. This will be allowed to air cure for 4 hours followed by water curing for 48 hours. The entire treatment will be taken upto 30 cm on parapet wall and tucked into groove in parapet all around. d) fourth and final layer of brick tilling with cement mortar (which will be paid for separately. For the purpose of measurement the entire treated surface will be measured)	sqm				
					GRAND TOTAL		
		Note:					
		1 .In case any obvious mistake the schedule of the item which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during period of contract .					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		
1	2	3	4	5	6	7

CONTRACTOR

CHIEF EXECUTIVE OFFICER