

**Name of Work : Sheet roofing to drying area of cloths to dhobi periphery yard of VPSV Ayurveda college
hospital kottakkal
TENDER SHEDULE**

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	850 kg	10.16.1 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved (apoxy) steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	kg			
2	70 sqm	50.12.2.1 Providing & fixing Poly carbonate corrugated sheet 0.8 mm thick as approved by the Engineer in charge and should be supplied in a single length of 12 M or as decide by the Engineer in charge. The sheets shall be fixed using self drilling / self tapping screw of size (5.5x55 mm) with EPDM seal complete upto any pitch in horizontal/ vertical/ curved surface, but excluding the cost of purlins, rafters, trusses, and including cutting to size shapes where ever required	sqm			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	3.3 kg	<p>OD-16/2020-21 Modified data from DSR no 21.7.1</p> <p>Providing and fixing machine moulded aluminium covering of approved pattern & design, made out of machine cut aluminium sheet and machine holed for receiving dash fastener, over expansion joints on vertical surfaces/ ceiling floors, the fixing on plate in one row on one side of joint only shall be done with stainless steel dash fastners of 8 mm dia and 75 mm long bolt including providing aluminium - washers 2 mm thick 15 mm dia, at a staggered pitch of 200 mm centre to centre including drilling holes in the receiving surface and providing expandable plastic sleeves in holes etc. complete as per drawing and direction of Engineer -in-charge.</p> <p>Anodised aluminium plane sheet 2.5 mm thick (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)</p>	kg			
4	50 sqm	<p>13.63.1</p> <p>Painting with aluminium paint of approved brand and manufacture to give an even shade.</p> <p>Two or more coats on new work</p>	sqm			
5	17 m	<p>OD-14/2020-21</p> <p>Supplying and fixing best quality PVC square type gutter 200 mm or nearest size with necessary all fittings</p>	m			
6	2 nos	<p>OD-15/2020-21</p> <p>Supplying and fixing best quality 200mm or nearest size PVC End bracket and drops including cost and conveyance of materials and labour charge etc.</p>	nos			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
7	9 m	12.41.2 Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	m			
8	3 m	12.42.5.2 Providing and fixing on wall face unplasticised- PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion Bend 87.50 110 mm bend	m			
		APPENDIX -B FLOOR FINISHING WORK				
1	70 sqm	2.28.1 Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	sqm			
2	0.5 m ³	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:	m ³			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	3.5 sqm	4.3.1 Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns	sqm			
4	60 sqm	16.68 Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of Coarse aggregates 6mm, filling the joints with Coarse aggregates 6mm etc. all complete as per the direction of Engineer-in-charge.	sqm			
5	1 nos	OD-2/20-21 , Modified data from DSR No 19.18.2 Supplying and fixing cast iron light duty manhole cover of size 600x600 mm. with frame.	nos			
					GRAND TOTAL	
		Note: 1 .In case any obvious mistake the schedule of the item which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during period of contract .				

CONTRACTOR

CHIEF EXECUTIVE OFFICER