

**Name of Work :RECONSTRUCTION OF DAMAGED LH BOUNDRY WALL AT GROUND SIDE**  
**TENDER SHEDULE**

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	10.560 cum	od97393/2023_2024 Demolishing brick, Laterite work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	cum			
2	0.550 cum	15.2.2 Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:4:8 leaner mix ( including equivalent design mix)	cum			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	4.200 cum	2.7.1 Earth work in excavation by mechanical means (Hydraulic excavator )/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. Ordinary rock	cum			
4	1.040 cum	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	cum			
5	8.740 cum	od87768/2023_2024 Departmental Laterate masonry with neatly dressed laterate stone of size 40x20x20cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc.	cum			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
6	1.201 cum	50.6.1.1 Solid block masonry using pre cast solid blocks ( factory made) of size 40x20x20cm or nearest available size confirming to IS 2185 part 1 of 1979 for foundation and plinth with thickness 20 cm and above in: CM 1:6 ( 1 cement : 6 coarse sand) etc complete	cum			
7	2.600 sqm	4.3.1 Centering and shuttering including strutting, propping etc. and removal of form work for:Foundations, footings, bases for columns	sqm			
8	0.520 cum	5.1.3 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 ( 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
9	45.000 kilogram	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	kg			
10	80.000 sqm	13.1.2 12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand).	sqm			
11	80.000 sqm	13.39.2 Colour washing such as green, blue or buff to give an even shade:New work (two or more coats) with a base coat of whiting	sqm			
					<b>GRAND TOTAL</b>	

CONTRACTOR

CHIEF EXECUTIVE OFFICER