Name of work: Land development in back side of Hospital payward in VPSV Ayurveda College, Kottakkal

Ta	Quantity	Description of work	Unit			Amount		
Item				In figure		In mondo	D. D.	
no				Rs.	Ps.	In words	Rs.	Ps.
1	2	3	4	5	i	6	7	
1	10 m³	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	/m³					
2	105 m²	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil	/m²					
3	4 Nos	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 30 cm girth upto and including 60 cm girth.	/E					
4	21 m³	Hard laterite neatly dressed stones of size 30x20x20 cm in cement mortar 1:6.	/m³					

CONTRACTOR CHIEF EXECUTIVE OFFICER

Item	Quantity	Description of work	Unit			Quoted rate	Amount	
				In figure		To an and a	D.	D.,
no				Rs.	Ps.	In words	Rs.	Ps
1	2	3	4	5		6		7
5	140 m³	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	/m³					
6	45 m²	12 mm cement plaster: 1:4 (1 cement : 4 fine sand).	/m²					
						TOTAL		

notice of the contractor during the period of contract.

CONTRACTOR CHIEF EXECUTIVE OFFICER