

Name of Work :Renovation of Ladies Hostel Sports room in VPSV Ayurveda college, Kottakkal

TENDER SCHEDULE

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
1	45 m ²	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos sheet	/m ² /m ²					
2	6 Nos	Dismantling and removing MS sections of rafters and purlins.	/E					
3	210 kg	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	/kg					
4	195 kg	Using departmental rafter and purlins. Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted	/kg					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5	6	7		
5	40 m ²	<p>sealant where required etc. but excluding the cost of purlins, rafters and trusses. 0.71 mm thick, the profile detail width 1044/920 mm, cover width 1000/875 mm. Providing at all heights, levels and locations Aluminium profile industrial troughed sheet of Alloy 31500/31000/40800, conforming to IS 1254, IS 737, IS 2676. The sheet shall be fixed using self drilling/self tapping SS screws of size 5.5x65 mm with EPDM seal complete upto required pitch in horizontal, vertical or curved surfaces i/c cutting to size and shape where required as per specifications, detail drawings and direction of Engineer-in-Charge. The rate shall be inclusive of all screws, seal, ridge, labour, scaffolding, machinery for fixing and approved sealant where required etc. but excluding the cost of purlins, rafters and trusses. 0.71 mm thick, the profile detail width 1044/920 mm, cover width 1000/875 mm.</p>	/m ² /m ²					
6	15 m	Supplying and fixing best quality PVC square type gutter 200 mm or nearest size with necessary all fittings .	/m					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity	Description of work	Unit	Quoted rate		Amount	
				In figure		Rs.	Ps.
				Rs.	Ps.		
1	2	3	4	5	6	7	
7	15 m ²	Providing & fixing Poly carbonate corrugated sheet 0.8 mm thick as approved by the Engineer in charge and should be supplied in a single length of 12 M or as decide by the Engineer in charge. The sheets shall be fixed using self drilling / self tapping screw of size (5.5x55 mm) with EPDM seal complete upto any pitch in horizontal/ vertical/ curved surface, but excluding the cost of purlins, rafters, trusses, and including cutting to size shapes where ever required.	/m ² /m ²				
8	36 kg	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	/kg				
9	14 m ²	Painting with aluminium paint of approved brand and manufacture to give an even shade . Two or more coats on new work	/m ²				
10	10 m ²	One or more coats on old work.Painting with aluminium paint of approved brand and manufacture to give an even shade: One or more coats on old work.	/m ² /m ²				

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
11	400 m ²	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)including Scarping and cleaning the surface	/m ² /m ²					
12	12 m	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	/m					
13	4 Nos	Supplying and fixing best quality 200mm or nearest size PVC End bracket and drops including cost and conveyance of materials and labour charge etc.	/E					
						TOTAL		
Note: In case any obvious mistakes in the schedule of the items which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during the period of contract.								

CONTRACTOR

CHIEF EXECUTIVE OFFICER