

Name of Work : Renovation to college parking shed in VPSV Ayurveda college, kottakkal
TENDER SCHEDULE

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5	6	7		
1	152 m2	Dismantling roofing including ridges, hips, valleys and gutters etc.,and stacking the material within 50 metres lead of: Asbestos sheet	/m2					
2	166 m2	Providing at all heights, levels and locations Aluminium profile industrial troughed sheet of Alloy 31500/31000/40800, conforming to IS 1254, IS 737, IS 2676. The sheet shall be fixed using self drilling/self tapping SS screws of size 5.5x65 mm with EPDM seal complete upto required pitch in horizontal, vertical or curved surfaces i/c cutting to size and shape where required as per specifications, detail drawings and direction of Engineer-in-Charge. The rate shall be inclusive of all screws, seal, ridge, labour, scaffolding, machinery for fixing and approved sealent where required etc. but excluding the cost of purlins, rafters and trusses. 0.40 mm thick, the profile detail width 1044/920 mm, cover width 1000/875 mm.	/m2					
3	182 m2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	/m2					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5	6	7		
4	205 Kg	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	/Kg					
5	135 m2	Painting with aluminium paint of approved brand and manufacture to give an even shade:two or more coats over a priming coat of iron primer.	/m2	90.00				
6	85 m2	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	/m2	97.00				
7	11 m3	Filling available excavated earth (excluding rock) in trenches, plinth,sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	/m3	165.00				
8	2 m3	plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	/m3					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5	6	7		
9	3 m2	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Columns, Pillars, Piers, Abutments, Posts and Struts	/m2					
10	130 m2	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	/m2					
11	10 m2	12 mm cement plaster of mix :1:4 (1 cement: 4 fine sand)	/m2					
					TOTAL			
Note: In case any obvious mistakes in the schedule of the items which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during the period of contract.								

CONTRACTOR

CHIEF EXECUTIVE OFFICER