

Name of Work :Connecting ETP water line to PG Block of VPSV Ayurveda college, Kottakkal .

TENDER SHEDULE

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6		7
1	1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m . Ordinary rock .	/m ³					
2	0.50	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	/m ³ /m ³					
3	5.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500 D or more.	/kg					
4	5.00	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	/m ² /m ²					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
5	30.00	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 50 mm dia 10Kgf/cm ² - External work - Exposed on wall including patch plastering and painting. .	/m					
6	1.00	Supplying and fixing 1000 L capacity syntex water tank (Hycount) .	/E					
7	66.00	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 40 mm dia 6 Kgf/cm ² - External work - Exposed on wall including patch plastering and painting.	/m					
8	270.00	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. this includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 6 Kgf/cm ² - External work - Exposed on wall including patch plastering and painting.	/m					
9	20.00	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead	/E					

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item No	Quantity	Description of work	Unit	Quoted rate		Amount		
				In figure		In words	Rs.	Ps.
				Rs.	Ps.			
1	2	3	4	5		6	7	
10	20.00	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity	/E					
11	95.00	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 20 mm dia 10Kgf/cm ² External work- Exposed on wall including patch plastering and painting.	/m					
12	2.00	Supplying and fixing 50 mm pvc ball valve with handle.	/E					
13	6.00	Supplying and fixing 40 mm pvc ball valve with handle.	/E					
14	9.00	Supplying and fixing 32 mm pvc ball valve with handle.	/E					
15	30.00	Supplying and fixing 15mm PVC best quality short body tap with hose connector.	/E					
						TOTAL		
Note: In case any obvious mistakes in the schedule of the items which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during the period of contract.								

CONTRACTOR

CHIEF EXECUTIVE OFFICER