

**Name of Work :Parapet for Hospital pay ward- second floor terrace**

**QUOTATION SCHEDULE**

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	1.162 cum	15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	cum			
2	7.155 cum	50.6.3.2 Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x10 cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level for 10 cm thick wall in : CM 1:6 ( 1 cement : 6 coarse sand) including cost of scaffolding complete	cum			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	83.20 sqm	13.4.2 12 mm cement plaster of mix:1:6 ( 1 cement : 6 coarse sand)	sqm			
					<b>GRAND TOTAL</b>	
		<b>Note:</b> <b>1 .In case any obvious mistake the schedule of the item which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during period of contract .</b>				

CONTRACTOR

CHIEF EXECUTIVE OFFICER