

**Name of Work :CONSTRUCTION OF RAINWATER HARVESTING FILTERS IN HOSPITAL
TENDER SHEDULE**

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	1.000 cum	2.8.1 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	cum			
2	1.000 cum	51.2.3 Filling with Quarry Muck Filling up low lying and water logged areas with local material/ quarry muck, spreading in layers, leveling the top at site and consolidation by ramming, etc complete for improving the CBR value of subgrade	cum			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	0.270 cum	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	cum			
4	5.000 cum	7.1.1 Random rubble masonry with hard stone in foundation and plinth including levelling up with cementconcrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with:Cement mortar 1:6 (1 cement : 6 coarse sand)	cum			
5	1.500 cum	5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size)	cum			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
6	105.000 kilogram	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	kg			
7	20.000 sqm	5.9.1 Centering and shuttering including strutting, etc. and removal of form for: Foundations, footings, bases of columns, etc for mass concrete	sqm			
8	21.000 sqm	13.1.2 12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand).	sqm			
					GRAND TOTAL	

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7

CONTRACTOR

CHIEF EXECUTIVE OFFICER