

Name of Work :PROVIDE POLY CARBONATE SHEET ROOFING FOR HOSPITAL RAMP ROOF SIDES.
TENDER SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure Rs.	In words	Rs.
1	2	3	4	5	6	7
1	185.553 kg	10.16.1 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finished welded type tubes	kg			
2	39.360 sqm	od149454/2022_2023 Providing & fixing Poly carbonate plain sheet 2 mm thick as approved by the Engineer in charge. The sheets shall be fixed using self drilling/ self tapping screw of size (5.5x55mm) with EPDM seal complete up to any pitch in horizontal / vertical / curved surfaces, but excluding the cost of purlins, rafters, trusses and including cutting to size and shapes where ever required, scaffolding charges are included.	sqm			
3	15.416 sqm	13.63.1 Painting with aluminium paint of approved brand and manufacture to give an even shade.Two or more coats on new work	sqm			
					GRAND TOTAL	

CONTRACTOR

CHIEF EXECUTIVE OFFICER