

Name of Work :TILE WORK AT LADIES HOSTEL
TENDER SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	35.003 sqm	15.23.1 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.For thickness of tiles 10 mm to 25 mm	sqm			
2	0.999 cum	15.2.2 Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge.Nominal concrete 1:4:8 leaner mix (including equivalent design mix)	cum			

CONTRACTOR

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	0.999 cum	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum			
4	20.000 m	50.18.7.6.2 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing . This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 50 mm dia 6 Kgf/cm ² - Internal work- Exposed on wall	m			

CONTRACTOR

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
5	5.000 sqm	22.5 Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours. b) Second layer of slurry of cement @ 0.242 kg /sqm mixed with water proofing cement compound @ 0.126 kg/ sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	sqm			

CONTRACTOR

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
6	35.003 sqm	11.38 Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of Ist quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 Coarse sand), including pointing the joints with white cement and matching pigments etc., complete.	sqm			
7	4.000 each	od155357/2022_2023 supplying and fixing 100 mm or nearest size PVC floor trap and stainless steel gratings(150mmx150mm) with all fittings, including cost and conveyance of all materials and labor charge etc.	E			
					GRAND TOTAL	

CONTRACTOR