

**Name of Work :REPLACING MENS HOSTEL ROOF GUTTERS AND TOILET REPAIR ETC**  
**TENDER SHEDULE**

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	54.000 m	od154829/2022_2023 Dismantling existing gutter and clamps etc. and stacking the materials within 50 meters. including all charges	m			
2	54.000 m	od154838/2022_2023 Supplying and fixing best quality PVC square type gutter 200 mm or nearest size with GI clamps at 1.00m spacing including cost and conveyance of materials and labour charges etc..	m			
3	8.000 each	od154839/2022_2023 supplying fixing PVC 200 mm best quality end trop/bracket/end top etc. joints including cost and conveyance and labour charge etc	E			
4	4.000 no	50.18.9.22.4 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement- 110 mm dia Bend	nos			

CONTRACTOR

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
5	12.000 sqm	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm			
6	25.500 sqm	13.1.1 12 mm cement plaster of mix:1:4 (1 cement :4 fine sand)	sqm			
7	15.000 sqm	13.46.1 Finishing walls with Acrylic Smooth exterior paint of required shade:New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	sqm			
8	1.703 sqm	15.23.1 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.For thickness of tiles 10 mm to 25 mm	sqm			
9	0.172 cum	15.2.2 Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge.Nominal concrete 1:4:8 leaner mix ( including equivalent design mix)	cum			

CONTRACTOR

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
10	0.482 cum	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum			
11	10.000 sqm	od168636/2022_2023 Neat cement flushing with color pigment .etc.complete	sqm			
12	2.100 sqm	22.5 Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours. b) Second layer of slurry of cement @ 0.242 kg /sqm mixed with water proofing cement compound @ 0.126 kg/ sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	sqm			

CONTRACTOR

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
13	1.000 each	17.13.2 Providing and fixing white vitreous china water closet squatting pan ( Indian type):Orissa pattern W.C. pan of size 580x440 mm	E			
14	5.000 m	50.18.8.9.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chased and making good the wall etc. 110 mm pipe 6kgf/cm <sup>2</sup>	m			
15	1.000 no	50.18.9.22.3 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement-110 mm dia Door Elbow	no			

CONTRACTOR

