

Name of Work :Providing interior works for surgical cosmetology OP in hospital.

QUOTATION SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
1	8.00	50.9.11.2 Providing and fixing Thomson Multi wood board or equivalent make paneling 18 mm thick, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately)as per the direction of site Engineer-in-charge	sqm			
2	4.20	od182542/2024_2025 Providing and fixing Thomson Multi wood board or equivalent make paneling 8 mm thick, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately) as per the direction of site Engineer- in- charge.	sqm			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
3	6.00	od182541/2024_2025 Providing and fixing kitchen cabinets wall mounding, panels and exterior uses etc. quality certifies and termite resistant ply wood 7 ply 16mm thick. conforming to IS 1328 BWR type. Including necessary fittings etc, all complete	sqm			
4	42.00	21.1.1.2 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle,Aluminnium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge.(Glazing, paneling and dash fasteners to be paid for separately):For fixed portionPowder coated aluminium (minimum thickness of powder coating 50 micron)	kg			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
5	3.40	21.2.2 Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS : 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge.Pre-laminated particle board with decorative lamination on both sides	sqm			
6	11.00	13.48.2 Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications:Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture	sqm			
7	54.00	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	sqm			

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
8	3.00	13.99.1 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work	sqm			
9	15.00	od176946/2024_2025 Providing and fixing false ceiling with 9.0 mm thick PVC plain panel board ceiling of approved quality in aluminium frame work with necessary screws etc complete (aluminium frame work shall be paid separately)	sqm			
10	16.00	od178529/2024_2025 Stainless steel SS304 grade, Auto hinges, soft close, Rust proof Cabinet Hinges	Nos			
11	8.00	9.165.1 Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete.125 mm	Nos			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		Rs.
1	2	3	4	5	6	7
12	1.951	od177844/2024_2025 Providing and fixing 6mm thick mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make . Rectangular mirror.	sqm			
13	12.00	od184476/2024_2025 Removing and refixing aluminium partition, door works after necessary repairs or reworks. etc complete as per the direction of site Engineer-in-charge.	sqm			
					GRAND TOTAL	
		Note: 1 .In case any obvious mistake the schedule of the item which can be easily identified, the contractor shall not take advantage of these errors and department reserves the right to correct these errors whenever they are noticed after formally bringing it to the notice of the contractor during period of contract .				

CONTRACTOR

CHIEF EXECUTIVE OFFICER